

P.O. Box 530985, St. Petersburg, FL 33747
(813) 610-2590

- Pipe threaded and made in the USA
- Schedule 80 PVC pipe
- NSF Approved
- 630 psi min. burst at 73°F
- Used in new construction before the meters are installed to flush out the piping system without contaminating the meters

TYPE	A	B	C
TUBE0450	4.5"	1"	0.95"
TUBE0750	7.5"	1"	0.95"
TUBE1075	10.75"	1.25"	1.25"
TUBE 2" x 12-5/8"	12.625"	2"	1.9"
TUBE 2-1/2" x 15-1/4"	15.25"	2.5"	2.3"

